

Doing the ‘grunt work’: Data integration in cross-domain sciences

Author

Ciara Zogheib, Faculty of Information, University of Toronto, Toronto, ON, Canada,
ciara.zogheib@mail.utoronto.ca

Statements and Declarations

Declaration of Conflicting Interests: The author declared no potential conflicts of interest with respect to the research, authorship, and/or publication of this article

Funding: The author received no financial support for the research, authorship, and/or publication of this article.

Ethical Approval: This study was approved by the University of Toronto’s Social Sciences, Humanities and Education Research Ethics Board (protocol number 45671) on January 8, 2024.

Data Availability: Raw data supporting this study cannot be publicly shared due to inclusion of identifying details (redacted where images appear in this paper).

Abstract

Cross-domain data integration is of interest to information scholars, but is generally poorly documented and evaluated indirectly—we know that interdisciplinary scientists work with data from multiple domain contexts, which differ in form, structure, and terminology, but not about how these data are integrated. In this paper, I explore the practice of cross-domain data integration by completing draw-and-write interviews about data practices at interdisciplinary science laboratories. I observe that cross-domain integration is conceived of by scientists as a data practice, but that the activities comprising this process are not formalized in the way that other data practices are. I demonstrate that interdisciplinary scientists conceive of cross-domain integration as trivial, data centric ‘grunt work’, distinct from and after-the-fact to ‘real’ scientific research, and draw on information scholarship to discuss the implications of this perspective for practice (people trying to *do* cross-domain integration) and for future scholarship (people trying to *study* cross-domain integration).

Background

Broad Data

A project using big data is often a project using data that are generated within multiple domain contexts—that is, ‘broad’ data—which take on different forms, are evaluated by different quality criteria, and adhere to different standards of documentation according to the norms of those domains (Shah et al., 2023; Hendler, 2014). Domains can include academic disciplines, communities of practice, and professional sectors; we can understand domains as groups with shared ontological and epistemological commitments (Fry and Talja, 2007; Hjørland, 2017). Domain analysis is well-established in the information sciences, and in recent years, data and computer science scholars have also adopted domain analytic approaches to explain data practice. For example, Ribes (2019) characterizes domains according to data formats, models, and schemas, as well as ‘fuzzier’ semantic features of data such as domain-specific metadata, terminology, and implicit assumptions, and others have explored how data practice differs in field-specific contexts (for example, see Hassett 2018; Donatz-Fest, 2024).

The touted benefits of big and broad data include the ability for scientists to make use of data from multiple sources and thus conduct more holistic analyses, enjoy increased coverage,

and see past domain-specific ‘blind spots’ (Housley et al., 2014; Feters and Molina-Azorin, 2017). In practice, it is not so straightforward to take advantage of broad data. It is not sufficient to merely gather large quantities of data from several domains, because each of these domains has shaped the data to meet certain criteria and take certain forms in accordance with that domain’s conventions. Attempts to integrate (alternately: synthesize, combine, converge) these broad data across domain boundaries result in friction due to differences in terminology, scale, error margins, and preferred methods of analysis (Edwards et al., 2011; Panagiotidou et al. 2022). To put it another way: cross-domain integration is a non-trivial undertaking, something that takes effort and impacts research outputs.

Cross-Domain Data Integration

We can surmise that integration of data across domains is something important that happens during research involving broad data. Our understanding of what cross-domain integration actually *is*, that is, of the specific activity or activities being undertaken, is less certain, because it is conceived of entirely differently in different areas of study. We can observe two broad ‘shapes’ in the literature on cross-domain integration: technical integration and social integration.

Computer science, data science, and statistics scholars tend to describe cross-domain integration in technical, object-focused terms. Such approaches have described integration as a process of ‘quantizing’ qualitative data generated in one domain setting so it can be incorporated into statistical models in others (Anguera et al., 2022; Batley, 2022; Shi et al., 2023), as implementing interdisciplinary databases capable of storing and linking data according to multiple domain standards (Pelizza, 2021), or as developing algorithms (Xu and Yu, 2017) and benchmarking protocols (Bashardoost et al., 2019) to structure exchange between heterogeneous datasets and knowledge bases. Here, integration is framed as something adjacent to interoperability or data-reuse. The defining characteristic of these technical conceptions of cross-domain integration is a focus on data artefacts and data-as-material, with little inquiry into what happens once the data are stored together or transformed into compatible formats—it is assumed implicitly that technical integration leads to effective use and conceptual understanding of broad data from across domains.

In a parallel and mostly non-overlapping discussion, cross-domain integration is instead framed in terms of collaboration, of knowledge sharing on a more social, human level. These

scholars propose theoretical frameworks for how people integrate (Schoonenboom, 2022; Boon and Van Baalen, 2019), examine practices that help and hinder collaboration for teams of scientists from multiple domains (Palmer, 2013; Parti and Szigeti, 2021), and conduct bibliometric studies of published research to demonstrate how cross-domain scholars cite and collaborate outside of their 'home domains' (Hu and Zhang, 2017; Laursen et al., 2022; Xu et al., 2025). These social framings of cross-domain integration tend to be either exclusively theoretical (not empirically validated) or retrospective (empirically studied *after* research has been completed, relying on people's recollection, citations, or on published methods sections of research articles). Here, the assumption is that integration took place, and the specific data materials involved in that process fall by the wayside.

There is a rich and growing literature on sociotechnical systems in the information sciences and more generally, in which scholars have demonstrated that data are socially constructed, products of the interaction of human actors *with* material and technical data artefacts (Thomer and Wickett, 2020; Bates et al., 2016; Orlikowski, 2007). At present, and with few exceptions (see for example Thomer, 2022 and Gazan, 2013), work on cross-domain integration tends not to draw on this scholarship. Even within the growing body of work by information scholars treating integration as a topic of relevance (for example, see Xu et al., 2025), the technical and social framings of cross-domain integration are largely insulated from each other. This is a missed opportunity. In considering technical *or* social framings of integration, studies tend to implicitly assume that one leads to the other without inquiring about why or how. By failing to explore in-depth the 'nitty gritty' of integration, along with the way that most empirical studies of integration are retrospective and/or based on citation networks of final publications, the actual activities of cross-domain integration undertaken during research are rarely articulated or documented, and thus become 'invisible' or 'forgotten' (Boix Mansilla, 2006; Wagner et al., 2011; Laursen et al., 2022). This is problematic: how can cross-domain, broad data research be trusted if a major part of the work (integration) is not documented and made subject to evaluation and review?

Open Questions

To address these gaps in the present understanding of how broad data are integrated, I suggest framing cross-domain integration as a data practice. By problematizing integration as a practice (rather than behaviour), we position the researcher interactions with data that comprise integration as something situated in the social context of a domain or domains (Savolainen,

2007), something subject, like any scientific practice, to rigorous critique (Reckwitz, 2002; Schatzki et al., 2001). We can find precedent for this approach in scholarship justifying the theory and empirically demonstrating its application (Blok et al., 2017; Christin, 2017). In adopting this approach, I take methodological inspiration from Bates et al.'s (2016) data journeys approach, and from Star and Griesemer's (1989) institutional ethnography, to center data-as-document, and as boundary object. I suggest that by 'following the data' and how scientists engage with it during cross-domain research, we will be able to observe how data transverse and transcend domain boundaries, and to understand practices of cross-domain integration not at present being directly observed in informational studies of the topic.

Using this framing, I completed draw-and-write interviews at interdisciplinary laboratories to explore two research questions: How do scientists' data practices shape their goals of cross-domain integration? *And, vice versa*, how do cross-domain research goals shape scientists' data practices?

This work will contribute to a growing body of information scholarship on cross-domain research, such as Xu et al. (2025) or Ma and Li (2022), and in particular will bring studies of cross-domain integration into conversation with existing literature about social-material-technical systems, including work in JASIST by Thomer (2022) or Given et al. (2024). Moreover, by directly observing and articulating the work being done during integration, I take steps toward encouraging serious consideration and documentation of integration as a research practice—in other words, making the invisible visible.

Methods and Data

Data Collection

The laboratory has long been a study site for exploring the sociomaterial and sociotechnical practices of science (Latour and Woolgar, 1979). Participants in this study are members of data-intensive interdisciplinary laboratories within existing research institutions. Here we are taking disciplines as our domains in question. We define 'data intensive science laboratories' as laboratories where research involves a significant big/broad data component in addition to traditional 'wet lab' research; participants self-identified as interdisciplinary researchers and have received funding for interdisciplinary projects. 'Existing research institutions' include universities and hospital- or government- affiliated laboratories. Participants

were recruited purposively from laboratories within the Greater Toronto Area, to facilitate in-person visits to laboratory locations. In total, five participants were interviewed. This sample size and recruitment approach does not allow for generalizable quantitative results, but is conventional for the qualitative, ‘thick’ description of each laboratory being sought here, and appropriate given the relatively high degree of trust necessary to elicit information about the messier or less polished parts of people’s research activities.

Data were collected through one-on-one, semi-structured ‘draw and write’ ethnographic interviews with participants, following Hartel (2019). Interviews took place at each participant’s laboratory site and were audio recorded, with the interviewer taking field notes to record context not captured in recordings. Questions were intentionally open-ended, proceeding roughly through the following thematic sections pertaining to the research topic:

1. People (Questions about domain backgrounds of scientists in the laboratory, challenges in bringing together different roles)
2. Data workflow (Questions aimed at understanding what kinds of data the laboratory generates, what technology are used, and how different domain data are integrated)
3. Context (Questions about participants’ views on broader trends in the field)

During section two, participants were invited to sketch and narrate a drawing of their laboratory’s data workflow (adopting best practices from Brailas’ 2020 paper and Hartel (2019)). The physical drawing was retained for analysis, and audio transcriptions transcribed. In transcripts and discussion of findings in this paper, participants and laboratory sites are referred to by generic pseudonyms to support anonymity (e.g. ‘Participant A’, ‘Site 1’). Portions of drawings that include individual lab members’ names are redacted for the same reason.

Data Analysis

Interview transcripts and field notes are analyzed using thematic analysis as described by Braun and Clarke (2012). This process is neither wholly deductive nor wholly inductive; rather, in the joint approach demonstrated by Byrne (2022), I explore text data with sensitizing concepts (i.e. existing theories of integration) in mind, but with openness to finding the as-yet-unknown themes that occur ‘around’ the subject. Analysis of workflow drawings has fewer consensus methodological precedents, and instead draws on a range of established approaches: I take inspiration from ‘conceptual modeling’ of socio-technical workflows to gain

insight about process and practices (Nalchigar and Yu, 2018; Recker et al., 2021), from Decuyper's (2020) 'visual network analysis' (particularly ideas of 'interfaces' between actors or data objects in a workflow as sites where cross-domain integration may be occurring), and from the visual analysis methods described by Hartel (2017) for analyzing hand-drawn diagrams and graphically organized written text in informational contexts.

Limitations

This study focused on scientific laboratories with multiple scientists doing interdisciplinary work, not on individual scientists doing other kinds of cross-domain work (e.g. transdisciplinary or antidisciplinary research) at a smaller scale or in non-scientific contexts. Future work could fill this gap by exploring the cross-domain data practices of humanities-focused scholars, and by considering integration as a practice undertaken by individual researchers, not necessarily synonymous with collaboration in a laboratory setting. Moreover, all participants in this study are investigators at laboratories affiliated with established research institutions. My focus on data work and cross-domain science in these settings is by no means a suggestion that data work and science are not done outside of institutional contexts. Cross-domain scholarship has strong connections to activist research and research intentionally situated outside of traditional academic settings (Carp et al., 2001; Schmidt, 2022), and this work has incorporated rigorous data practice since its origins (D'Ignazio and Klein, 2020).

Another unavoidable challenge in this work is in operationalizing a definition of cross-domain integration. As discussed in the previous sections of this paper, discourse on integration is fragmented, with the term at times being used interchangeably with others like 'synthesis', 'crossover', 'translation', or 'exchange' (Lang et al., 2012). This lack of definitional precision does not mean that cross-domain integration is not happening during cross-domain research—indeed, all participants used the words 'integration' or 'synthesis' to describe parts of their interdisciplinary research process—but rather, supports the motivation for this study, the idea that integration as data practice matters, and is taking place, but is at present poorly understood and documented.

Findings

“It’s A Lot”: Struggles of Cross-Domain Work

In existing scholarship on interdisciplinarity and cross-domain collaboration, certain themes such as funding challenges, issues with communication, and a sense of isolation from traditional academic communities, occur repeatedly (Manathunga et al., 2009; Shah et al., 2023). The present study is no exception. Four out of five participants (all but Participant C) raised the subject of funding without prompting, and three explicitly linked difficulties in being awarded funding to the cross-domain nature of their research. Per Participant E, the work of interdisciplinarity is “actually very valuable, but I don’t know how valued it is”, while Participant B expressed that “incentives are often not aligned for multidisciplinary collaborations.” Participant A diagnosed the issue further by saying that, “lots of funding bodies say they want new big ideas, but they don’t. They want incremental science. And I guess what I would say is I feel like I’ve built a career in thumbing my nose at people who want incremental science.” These challenges do not stop at obtaining funding: scientists expressed challenges with communication, particularly with ‘translation’ of domain-specific terminology, and a sense of isolation from their academic communities. Participant E said that their cross-domain research means they have “imposter syndrome in two disciplines” due to being an expert at neither, and Participant A repeated, “as I say to people over and over again, I have no idea what I’m doing.”

I begin by reporting these findings not because they are groundbreaking—as stated, they support similar findings from elsewhere in the literature—but because, though not directly data-related, these concerns from participants serve as important context for our exploration of cross-domain data work. Our interviews show that the scientists conducting cross-domain research are doing so with a sense of ‘breaking new ground’, doing something without an existing standard or correct approach. This lack of procedural certainty and precedent manifests in how participants understand (or *don’t* understand) the data practices of integration.

The Integration Gap

Participants were asked to sketch out their laboratories’ data workflows with the goal of identifying the part(s) of the process where cross-domain integration happens. While completing these drawings, participants provided extremely detailed descriptions—verbally and in their workflow sketches—of how and from where they produced or collected their data, as well as the

formats data took in its raw form and after pre-processing (generally text files, spreadsheets, and images). Most participants were able to describe the software used for data analysis, usually Python, R, Julia, or proprietary, domain-specific tools, and the ways that their lab stores data (e.g. institutionally or commercially-hosted cloud servers, SQL databases). Some offered to show examples of specific spreadsheets or database front-ends and walked the interviewer through their data materials in even more detail. Clearly, scientists at cross-domain laboratories, even when they took care in our interviews to emphasize that they are not data scientists or computer scientists, have strong data literacy and possess vocabularies with which to discuss their data practices. This makes it all the more noteworthy that, while all participants mentioned integration as part of their work, all participants also struggled to articulate how they integrate data from across domains.






Fig. 1. Workflow sketches from Participants D, C, and B (clockwise from top left). Red arrows point at 'integration' components of data workflows. Redacted components of images (covered by black rectangles) contain names of individuals or organizations.

When examining data workflow sketches, we can follow from Decuyper's (2020) strategies for visual network analysis and focus our attention on 'interfaces', or sites where distinct actors and data objects in a workflow come together. These interfaces are of interest to us as steps in the research process where data become boundary objects and cross-domain integration is likely to be occurring. In the data workflows drawn by participants, data collection steps tended to be described in domain-specific terms (e.g. "sociological data") until a single integration interface (as opposed to integration as an ongoing or multi-step practice) that usually occurred toward the end of research data workflows. Where prior data collection and curation steps included additional detail in words (e.g. file types, explanations of data sources) or illustrative drawings, integration steps often stood alone. As shown in Figure 1, Participant C wrote 'INTERPRETATION', Participant B drew a human stick figure and described it aloud as "doing the analysis" and "developing new tools", and Participant D wrote and circled the word 'STORY'. When asked to elaborate on these integration stages of their data workflows, participants lacked the certainty with which they had discussed the rest of their lab's data work. Taking Participant D as a particularly colourful example, they initially narrated the 'STORY' step in their workflow sketch as a "compression step, I guess, where we integrate these and we think about story" (evocative of ideas of cross-domain integration as compression described and disputed elsewhere; see Anguera et al. (2022) and Rovane (2010)). When asked to elaborate on what they meant by 'compressing' and 'integrating' data, the scientist replied,

"I don't know, haven't done it yet on this project... um... I'm terrified of this. I really don't know how to do it and there's more than one student and so you think about like, who takes ownership, and do you like have each student lead one substory? Uh, so there's problems- there's tensions of methods and ownership, um, and different disciplinary norms about paper length, authorship styles, authorship lists, and... uh... [10 second pause] I'm trying to think of an example I have for you, where I have actually published a mixed methods something... [laughs] I don't have any."

Participant D then walked the interviewer through a second data workflow of another project from their lab, and again, when prompted to elaborate about the integration interface, struggled

to illustrate or describe how different domain data components would be brought together, concluding that,

“certainly I think my data handling methods would be well characterized by ‘haphazard’ and certainly not explicit or considered or purposeful or anything like that, and that would not be offensive in the slightest.”

This lack of defined practice for integrating data and data work from different domains was characteristic across all interviews, and reflective of concerns from critics of cross-domain research that, even in the most rigorous research settings, the absence of a documented, formalized approach to integration means that *this component* of cross-domain research workflows cannot be properly evaluated and thus lacks rigour (Graff, 2016; Jacobs and Frickel, 2009; Pasipamire and Masuku, 2022). The question then becomes: if cross-domain integration is not at present a formal research practice, what *informal* activities are taking place during this stage of research?

One approach (taken by Participant D) is to have different lab members each work on ‘substories’ or individual components of a research project most relevant to their domain training then combine completed findings in a shared final publication. A potential issue with this approach is that, if research data are being collected, analyzed, and interpreted in domain-specific ‘substories’, with any integration only occurring during the writing of a final paper, it is unclear whether impactful cross-domain exchange is taking place. Indeed, this concern came up during the interviews, when Participant D spoke about how despite their intentions, data from one domain did not significantly impact or interact with data from the other. The second, most common approach to cross-domain integration offered by participants was to avoid it, or at least to minimize it, while still framing their research as interdisciplinary. Participants A and B described how projects are categorized into one of the domains relevant to their labs, and the team member with expertise in that domain takes the lead and situates the (still ostensibly interdisciplinary) project in the chosen domain. Explanation from Participant E may provide insight as to why this strategy is adopted: it goes, as much interdisciplinary research does, back to the issue of funding. When applying for grants, said Participant E, “I have to always kind of bend it a little bit and be like, this is the physics part of my research, or this is the stats part of my research, and like, write it in that way, because there isn't something that fits just right.” This phenomenon, where one domain dominates what is intended as a cross-domain endeavour, is

called ‘disciplinary capture’, and can limit the benefits cross-domain research is supposed to provide (Brister, 2016).

To summarize, we can take away that cross-domain integration is something that, at least in part, occurs through data and related work, but, in contrast to other parts of research data workflows (e.g. collection, processing), the activities of integration are not considered in advance or formalized by scientists. This results in the adoption of informal integration practices that potentially limit the utility of cross-domain collaboration.

“Grunt Work”: Data as Domain

We have seen the ways that data functions (or is supposed to function) as the medium of integration across multiple scholarly domains, but at times, our participants also approached data work as a domain in itself. In these cases, the practice in question became not the integration of data artefacts from multiple domains, but the integration of data work into what is conceived as a non-data-focused, cross-domain scientific workflow. We can make two key observations about this framing of cross-domain data practice.

The first is that scientists differentiate between scientific components of their research and the data work completed in support of that science. We can observe this dichotomy of data work versus ‘real’ research as (for example), Participant C made a distinction between “this group here who can run those pipelines, and these guys up here, the scientists who really are interested in what the results are”, and Participant B commented that among interdisciplinary science labs more generally, “no one remembers that they’re going to need to analyze it until the data comes in, I get so many last minute requests for people to- you know, I- ‘we need this analyzed and out the door and we don’t have anyone for it, do you have anyone to spare?’” A similar difference is made in participants’ workflow sketches, where data-centric steps are labeled with names of software, file types, or words such as ‘pre-processing’ and ‘cleaning’, while later interpretation steps—still reliant on the same data—are more often labeled with names of individual scientists in the lab. In doing so, data work is conceptualized as something automatic and instrumentalized, whereas data *interpretation* as positioned as science completed by thinking, communicating human experts, even when participants made clear verbally that humans are involved at every stage. Data work is thus framed as incidental to cross-domain science, rather than as part of that science.




Fig. 2. A data workflow sketch from Participant A. The red line down the middle of the image divides the lab's workflow into data processing and modeling as separate parts of the work. Redacted components of image (covered by black rectangles) contain first names of lab members.

The second emerging trend from participants' conceptions of data-work-as-domain subservient to 'primary' research domains was a further hierarchical differentiation between *kinds* of data work. We can see this idea in Figure 2, where Participant A drew a red line dividing their laboratory workflow into data processing and storage (written label as 'software') versus model development and analysis. Similarly, Participant B described how, "everybody wants to do the fancy tool development here [pointing at drawing, later stage of research] and nobody wants to run this bit [pointing at drawing, earlier stages of research]... nobody wants to do the grunt work in the middle." The implicit value judgment made about data 'grunt work' even in data-intensive research laboratories is reflective of a widespread devaluation of this work, only being addressed in recent years, that has potentially severe consequences for data quality and procedural rigour (Jo and Gebru, 2020; D'Ignazio and Klein, 2020; Sambasivan et al., 2021; Muller and Strohmayer, 2022). It is worth noting that Participant C offered a contrasting perspective, stating that the advent of big data and high-performance computing resources has fundamentally shifted their primary domain into, "essentially an information science"—this stance on data work was the exception, not the rule.

Discussion

In light of these findings, we can revisit our research questions. With respect to question A, '*How do scientists' data practices shape how they integrate across domains?*', we have observed that data are collected and processed primarily in single-domain workflows, even in interdisciplinary lab settings, and that these siloed data practices result in struggles with integration of the data, which seems to occur only toward the end of research workflows. We have seen that cross-domain integration *is* conceived of by scientists as a data practice, and occurs as one in laboratory settings, but that the activities comprising this practice are not formalized as such. To research question B, then, '*How do cross-domain research goals shape scientists' data practices?*', our answer seems to be that, bluntly, they don't. Scientists know their labs' data workflows and practices extremely well, *except* as pertains to cross-domain integration. Data work tends to happen according to single-domain standards, considered minimally relevant to the scientific goals of the project, and cross-domain integration is, apparently, a later event that just 'happens'. In the discussion that follows, I consider the implications of these findings for practice (i.e. for people trying to *do* cross-domain integration) and for future scholarship (i.e. for people, particularly information scholars, trying to *study* cross-domain integration).

Practical Impact

The implications of the observed failure to articulate and document the activities of cross-domain integration to the same standard that we expect researchers to articulate other research data practices are concerning: Thomer et al. (2022) make the case that when data work becomes 'invisible', it becomes impossible to understand the impact of specific actions on research outputs or on other steps in the research process. This can have adverse impacts on reproducibility (Gundersen, 2021), which is already a particular issue in the context of interdisciplinary and cross-domain research (Wagner et al., 2011), and on the ability of peers and regulatory bodies to evaluate cross-domain research—for example, by subjecting evaluations to outcome bias, where positive outcomes can obfuscate the impact of randomness or invalid methodological choices (Fanelli, 2012; Brownback and Kuhn, 2019). Moreover, government agencies cite the integration of broad data as a priority (Zogheib and Mahetaji, 2024), and much cross-domain data work is practical in nature and applied to address particular problems such as climate change, social determinants of health, and national security. The

minimal attention devoted to integration as a data practice, and the general lack of transparency and accountability for the actions comprising this practice, when the *results* of integration have direct effects on people's lives, health, and privacy, should be a concern to any researcher conscious of the social impacts of their work.

We have seen that integration is part of cross-domain scientific workflows and impacts the conclusions that scientific research reaches. Thus, in the same way that issues of reproducibility, transparency, and accountability of data science in general are addressed through documentation-based solutions such as model cards (Mitchell et al., 2019) and datasheets (Gebru et al., 2021), I suggest that the most actionable way forward is to prioritize giving cross-domain scientists the tools and vocabulary with which to articulate what they are doing when they say they are integrating across domains. Rather than prescribing how scientists *should* integrate broad data, we can aim in future work to produce scaffolding so that cross-domain and interdisciplinary scientists can document their integrative decisions and activities, improving accountability and transparency of the resulting research outputs. We can build here on work by Thomer et al. (2018), who emphasize the necessity of dataset documentation that captures the 'context of production'. Thomer et al. propose Research Process Modeling, a method with integration as a stated goal, through which researchers can document both computational and non-computational parts of the research process, modeling people, activities, decision points, and artefacts. The benefit of a documentation-based solution—whether it takes the form of a question guide or a research process model—is that it is flexible enough to encompass the wide range of strategies and activities that fall under the 'integration' umbrella (Keestra et al., 2022), and that it leaves room for the possibility of integration not as a single point in a data workflow, but as an ongoing, iterative practice of engagement with data across domains.

Future Scholarship

As well as demonstrating a need to better document the activities of cross-domain integration, the findings of this project also suggest new avenues for research *about* cross-domain, integrative research approaches. I introduce two here.

The first: a return to the workflow drawings elicited here shows that the nodes of these diagrams are not just data artefacts, but also material evidence, digital data sources, institutions, and the names of individuals or teams. Cross-domain integration is, according to the

scientists doing it, a social-material-technical process, and—as I suggested in the ‘Background’ section of this paper—would benefit from being studied as such. The divide between socially-focused and technologically-focused understandings of integration that currently persists in studies of cross-domain and interdisciplinary scholarship is, we have seen, not reflected in the actual practices of scientists doing this work, nor is it standard in science and technology studies or information studies more broadly, which acknowledge the interconnectedness of the social, material, and digital aspects of research. As a recent example of this kind of work, we can consider Belli’s (2021) ethnographic study of researchers at different international institutions, which expands on Basov’s (2018) socio-material networks framework to map relationships and usage patterns between actors of both analog and digital objects. We haven’t seen this lens applied explicitly to cross-domain research, but Palmer’s foundational 2013 study of an interdisciplinary research centre lays some useful groundwork. She discusses the information resources (analog and digital) used by scholars at the centre, as well as information search techniques adopted by interdisciplinary scholars “to promote discovery for synthesis” (p. 136). At the same time, she writes that,

“There is no overlay of technology that can permeate the organizational, intellectual, and linguistic barriers that constrain the flow and exchange of information across disciplines.”
(p. 2).

I do not suggest that technology overlays or dominates human activities of integration, but I do argue that it, along with material artefacts of research, permeates these activities, shaped by and shaping social and interactive aspects of cross-domain work. A holistic study of integration must be attuned to all three elements (e.g. as in the case of Panagiotidou et al., 2022); more work of this nature would address a gap in the literature on cross-domain practice. The field of information studies, with its problematizing of data and digital work, is well-positioned to contribute here.

A second, related thread to be pursued from the present study is on the hierarchy of data ‘grunt work’ and scientific work described by participants. Discussions of this tension are not without precedent, as Ribes (2019) touches on the at-times fraught relationship between computational work and the other domains to which that work is often of service and Muller & Strohmayer (2022) detail social and political forces resulting in the ‘forgetting’ of data work, but the issue only becomes more pressing as the impacts of big and broad data (and the accompanying tools and methodological innovations) are increasingly relevant across areas of

research (Anderson, 2008; Kremser and Brunauer, 2019). As Participant C in the present study shared, several scientific domains have become “essentially an information science”. It is worth exploring why, given the centrality of data work to much of contemporary research, perceptions of data work as less skilled or important to the scientific project persist. Future scholarship on this topic might build on literature that treats the relative disregard for research data work as a labour issue, centring the “modest labours” (Nadim, 2016, p. 515) that underlie much of contemporary science and questioning the potential gendering and geographical trends that contribute to the erasure of the care work of data curation and processing (Newlands, 2021; Davies and Holmer, 2024). Alternately, for a research direction that stays within our cross-domain context, we might follow Moats (2021) in conducting intervention-based, participatory research that asks subject matter experts with primarily qualitative, non-technical research programmes to engage with computational and data-focused tools to observe (and develop strategies to mitigate) the ‘messy interactions’ (p. 20) and integrative activities that ensue.

Efforts to pursue of these potential topics of research can have similar beneficial outcomes to the practical changes proposed previously: if we take cross-domain integration seriously as a practice to be undertaken or studied, we better position ourselves to evaluate that practice and its outputs more fairly—or, borrowing from Kestra et al. (2022), to adopt new and innovative forms of integration from an informed starting point.

Conclusion

Here I have presented the results of draw-and-write interviews with scientists at data-intensive, interdisciplinary laboratories on the subject of cross-domain integration. These conversations have revealed a need for improved consideration and documentation of the practice of integration at the working level, presented opportunities to study integration as a jointly social, material, and technical practice, and demonstrated how perceptions of data work as less important than other scientific knowledge work persist in cross-domain settings. The present study contributes to a growing body of information studies literature that explores the activities of cross domain research and makes the case for integration—of multiple domains, of big, broad, and multi-sourced data—as a practice requiring study and evaluation, not as something that ‘just happens’ and can be handwaved away.

Works Cited

- Anderson, C. (2008). *The End of Theory: The Data Deluge Makes the Scientific Method Obsolete*. Wired, 16(07). <https://statlit.org/pdf/2008EndOfTheory-DataDelugeMakesScientificMethodObsolete-WiredMagazine.pdf>
- Anguera MT, Castañer M, Portell M, et al. (2022) Bayesian Integration Applications in Physical Activity and Sport Research. In: *The Routledge Handbook for Advancing Integration in Mixed Methods Research*. 1st ed. London: Routledge, pp. 231–247.
- Basov, N. (2018). Socio-material network analysis: A mixed method study of five European artistic collectives. *Social Networks*, 54, 179–195.
<https://doi.org/10.1016/j.socnet.2018.02.003>
- Bates J, Lin Y-W and Goodale P (2016) Data journeys: Capturing the socio-material constitution of data objects and flows. *Big Data & Society* 3(2): 205395171665450.
- Batley PN (2022) Use of Bayesian Estimation in the Context of Fully Integrated Mixed Methods Models. In: *The Routledge Handbook for Advancing Integration in Mixed Methods Research*. 1st ed. London: Routledge, pp. 248–258.
- Belli, S. (2021). Affordance in Socio-Material Networks: A Mixed Method Study of Researchers' Groups and Analog-Digital Objects. *Frontiers in Psychology*, 12, 672155.
<https://doi.org/10.3389/fpsyg.2021.672155>
- Blok A, Carlsen HB, Jørgensen TB, et al. (2017) Stitching together the heterogeneous party: A complementary social data science experiment. *Big Data & Society* 4(2). SAGE Publications Ltd: 2053951717736337.
- Boix Mansilla V (2006) Assessing expert interdisciplinary work at the frontier: an empirical exploration. *Research Evaluation* 15(1): 17–29.
- Boon M and Van Baalen S (2019) Epistemology for interdisciplinary research – shifting philosophical paradigms of science. *European Journal for Philosophy of Science* 9(1): 16.
- Brailas A (2020) Using Drawings in Qualitative Interviews: An Introduction to the Practice. *The Qualitative Report*. Epub ahead of print 20 December 2020.
- Braun V and Clarke V (2012) Thematic analysis. In: *APA Handbook of Research Methods in Psychology, Vol 2: Research Designs: Quantitative, Qualitative, Neuropsychological, and*

Biological. APA handbooks in psychology®. Washington, DC, US: American Psychological Association, pp. 57–71.

Brister E (2016) Disciplinary capture and epistemological obstacles to interdisciplinary research: Lessons from central African conservation disputes. *Studies in History and Philosophy of Science Part C: Studies in History and Philosophy of Biological and Biomedical Sciences* 56: 82–91.

Brownback A and Kuhn MA (2019) Understanding outcome bias. *Games and Economic Behavior* 117: 342–360.

Byrne D (2022) A worked example of Braun and Clarke's approach to reflexive thematic analysis. *Quality & Quantity* 56(3): 1391–1412.

Christin A (2017) Algorithms in practice: Comparing web journalism and criminal justice. *Big Data & Society* 4(2). SAGE Publications Ltd: 2053951717718855.

Davies, S. R., & Holmer, C. (2024). Care, collaboration, and service in academic data work: Biocuration as 'academia otherwise.' *Information, Communication & Society*, 27(4), 683–701. <https://doi.org/10.1080/1369118X.2024.2315285>

Decuyper M (2020) Visual Network Analysis: a qualitative method for researching sociomaterial practice. *Qualitative Research* 20(1): 73–90.

D'Ignazio C and Klein LF (2020) *Data Feminism*. Strong ideas series. Cambridge, Massachusetts: The MIT Press.

Edwards PN, Mayernik MS, Batcheller AL, et al. (2011) Science friction: Data, metadata, and collaboration. *Social Studies of Science* 41(5). SAGE Publications Ltd: 667–690.

Fanelli D (2012) Negative results are disappearing from most disciplines and countries. *Scientometrics* 90(3): 891–904.

Fetters MD and Molina-Azorin JF (2017) The Journal of Mixed Methods Research Starts a New Decade: The Mixed Methods Research Integration Trilogy and Its Dimensions. *Journal of Mixed Methods Research* 11(3). SAGE Publications: 291–307.

Fry J and Talja S (2007) The intellectual and social organization of academic fields and the shaping of digital resources. *Journal of Information Science* 33(2): 115–133.

Gazan, R. (2013, February 12). Identifying Crossover Documents in an Interdisciplinary Research Environment. *iConference 2013*, Ft. Worth, TX.

- Gebru T, Morgenstern J, Vecchione B, et al. (2021) Datasheets for datasets. *Communications of the ACM* 64(12): 86–92.
- Given, L. M., Polkinghorne, S., & Cattlin, J. (2024). Structural elements and spheres of expertise: Creating a healthy ecosystem for cultural data initiatives. *Journal of the Association for Information Science and Technology*, 75(10), 1070–1086. <https://doi.org/10.1002/asi.24849>
- Graff HJ (2016) The “Problem” of Interdisciplinarity in Theory, Practice, and History. *Social Science History* 40(4). Cambridge University Press: 775–803.
- Gundersen OE (2021) The fundamental principles of reproducibility. *Philosophical Transactions of the Royal Society A: Mathematical, Physical and Engineering Sciences* 379(2197). Royal Society: 20200210.
- Hartel J (2017) Adventures in Visual Analysis. *The Visual Methodologies Journal (Special Issue: Fourth International Visual Methods Conference)* 5(1): 80–91.
- Hartel J (2019) *Draw-and-Write Techniques*. SAGE Research Methods Foundations. SAGE Publications Ltd.
- Hassett BR (2018) Which Bone to Pick: Creation, Curation, and Dissemination of Online 3D Digital Bioarchaeological Data. *Archaeologies* 14(2): 231–249.
- Hendler J (2014) Data Integration for Heterogenous Datasets. *Big Data* 2(4): 205–215.
- Hjørland B (2017) Domain analysis. *Encyclopedia of Knowledge Organization*. ISKO.
- Housley W, Procter R, Edwards A, et al. (2014) Big and broad social data and the sociological imagination: A collaborative response. *Big Data & Society* 1(2). SAGE Publications Ltd: 2053951714545135.
- Hu J and Zhang Y (2017) Discovering the interdisciplinary nature of Big Data research through social network analysis and visualization. *Scientometrics* 112(1): 91–109.
- Jacobs JA and Frickel S (2009) Interdisciplinarity: A Critical Assessment. *Annual Review of Sociology* 35. Annual Reviews: 43–65.
- Jo ES and Gebru T (2020) Lessons from Archives: Strategies for Collecting Sociocultural Data in Machine Learning. *Proceedings of the 2020 Conference on Fairness, Accountability, and Transparency*: 306–316.

- Keestra, M., Uilhoorn, A., & Zandveld, J. (2022). Pluralism in Teaching Interdisciplinary Research: The Amsterdam Institute for Interdisciplinary Studies Textbook. *Issues in Interdisciplinary Studies*, 40(1), 55–73.
- Kremser, W., & Brunauer, R. (2019). Do we have a Data Culture? In P. Haber, T. Lampoltshammer, & M. Mayr (Eds.), *Data Science – Analytics and Applications* (pp. 83–87). Springer Fachmedien. https://doi.org/10.1007/978-3-658-27495-5_11
- Lang, D. J., Wiek, A., Bergmann, M., Stauffacher, M., Martens, P., Moll, P., Swilling, M., & Thomas, C. J. (2012). Transdisciplinary research in sustainability science: Practice, principles, and challenges. *Sustainability Science*, 7(1), 25–43.
- Latour B and Woolgar S (1979) *Laboratory Life: The Construction of Scientific Facts*. Princeton University Press.
- Laursen BK, Motzer N and Anderson KJ (2022) Pathways for assessing interdisciplinarity: A systematic review. *Research Evaluation* 31(3): 326–343.
- Ma, R., & Li, K. (2022). Digital humanities as a cross-disciplinary battleground: An examination of inscriptions in journal publications. *Journal of the Association for Information Science and Technology*, 73(2), 172–187. <https://doi.org/10.1002/asi.24534>
- Manathunga C, Pitt R and Critchley C (2009) Graduate attribute development and employment outcomes: tracking PhD graduates. *Assessment & Evaluation in Higher Education* 34(1). Routledge: 91–103.
- Mitchell M, Wu S, Zaldivar A, et al. (2019) Model Cards for Model Reporting. *Proceedings of the Conference on Fairness, Accountability, and Transparency*: 220–229.
- Muller M and Strohmayer A (2022) Forgetting Practices in the Data Sciences. In: *Proceedings of the 2022 CHI Conference on Human Factors in Computing Systems*, New York, NY, USA, 29 April 2022, pp. 1–19. CHI '22. Association for Computing Machinery.
- Nadim, T. (2016). Data Labours: How the Sequence Databases GenBank and EMBL-Bank Make Data. *Science as Culture*, 25(4), 496–519. <https://doi.org/10.1080/09505431.2016.1189894>
- Nalchigar S and Yu E (2018) Business-driven data analytics: A conceptual modeling framework. *Data & Knowledge Engineering* 117: 359–372.
- Newlands, G. (2021). Lifting the curtain: Strategic visibility of human labour in AI-as-a-Service. *Big Data & Society*, 8(1), 205395172110160. <https://doi.org/10.1177/20539517211016026>

- Orlikowski, W. J. (2007). Sociomaterial Practices: Exploring Technology at Work. *Organization Studies*, 28(9), 1435–1448. <https://doi.org/10.1177/0170840607081138>
- Palmer CL (2013) *Work at the Boundaries of Science: Information and the Interdisciplinary Research Process*. Springer Science & Business Media.
- Panagiotidou G, Poblome J, Aerts J, et al. (2022) Designing a Data Visualisation for Interdisciplinary Scientists. How to Transparently Convey Data Frictions? *Computer Supported Cooperative Work (CSCW)* 31(4): 633–667.
- Parti K and Szigeti A (2021) The Future of Interdisciplinary Research in the Digital Era: Obstacles and Perspectives of Collaboration in Social and Data Sciences - An Empirical Study. *Cogent Social Sciences* Serpa S (ed.) 7(1): 1970880.
- Pasipamire N and Masuku M (2022) Paradigmatic Foundations of Mixed Methods Research: The Incompatible Thesis of Mixing Belief Systems. In: *Handbook of Research on Mixed Methods Research in Information Science*. IGI Global, pp. 87–101.
- Pelizza A (2021) Towards a sociomaterial approach to inter-organizational boundaries: How information systems elicit relevant knowledge in government outsourcing. *Journal of Information Technology* 36(2). SAGE Publications Ltd: 94–108.
- Recker J, Lukyanenko R, Jabbari M, et al. (2021) From Representation to Mediation: A New Agenda for Conceptual Modeling Research in a Digital World. *MIS Quarterly* 45(1). MIS Quarterly: 269–300.
- Reckwitz A (2002) Toward a Theory of Social Practices: A Development in Culturalist Theorizing. *European Journal of Social Theory* 5(2). SAGE Publications Ltd: 243–263.
- Ribes D (2019) How I Learned What a Domain Was. *Proc. ACM Hum.-Comput. Interact.* 3(CSCW): 38:1-38:12.
- Rovane C (2010) Why Scientific Realism May Invite Relativism. In: Caro M de and Macarthur D (eds) *Naturalism and Normativity*. Columbia University Press.
- Sambasivan N, Kapania S, Highfill H, et al. (2021) “Everyone wants to do the model work, not the data work”: Data Cascades in High-Stakes AI. In: *Proceedings of the 2021 CHI Conference on Human Factors in Computing Systems*, New York, NY, USA, 7 May 2021, pp. 1–15. CHI '21. Association for Computing Machinery.

- Savolainen R (2007) Information Behavior and Information Practice: Reviewing the “Umbrella Concepts” of Information-Seeking Studies. *The Library Quarterly* 77(2). The University of Chicago Press: 109–132.
- Schatzki TR, Knorr-Cetina K and Savigny E von (eds) (2001) *The Practice Turn in Contemporary Theory*. New York: Routledge.
- Schmidt JC (2022) *Philosophy of Interdisciplinarity: Studies in Science, Society and Sustainability*. History and philosophy of technoscience 20. Abingdon, Oxon: Routledge.
- Schoonenboom J (2022) Developing the Meta-Inference in Mixed Methods Research through Successive Integration of Claims. In: *The Routledge Handbook for Advancing Integration in Mixed Methods Research*. Taylor & Francis.
- Shah SH, O’Lenick CR, Wan JS, et al. (2023) Connecting Physical and Social Science Datasets: Challenges and Pathways Forward. *Environmental Research Communications*. Epub ahead of print 4 September 2023. DOI: 10.1088/2515-7620/acf6b4.
- Shi X, Pan Z and Miao W (2023) Data integration in causal inference. *WIREs Computational Statistics* 15(1): e1581.
- Star SL and Griesemer JR (1989) Institutional Ecology, ‘Translations’ and Boundary Objects: Amateurs and Professionals in Berkeley’s Museum of Vertebrate Zoology, 1907–39. *Social Studies of Science* 19(3). SAGE Publications Ltd: 387–420.
- Thomer AK (2022) Integrative data reuse at scientifically significant sites: Case studies at Yellowstone National Park and the La Brea Tar Pits. *Journal of the Association for Information Science and Technology* 73(8): 1155–1170.
- Thomer AK and Wickett KM (2020) Relational data paradigms: What do we learn by taking the materiality of databases seriously? *Big Data & Society* 7(1): 205395172093483.
- Thomer AK, Akmon D, York JJ, et al. (2022) The Craft and Coordination of Data Curation: Complicating Workflow Views of Data Science. *Proceedings of the ACM on Human-Computer Interaction* 6(CSCW2): 414:1–414:29.
- Wagner CS, Roessner JD, Bobb K, et al. (2011) Approaches to Understanding and Measuring Interdisciplinary Scientific Research (IDR): A Review of the Literature. *Journal of Infometrics* 5. Elsevier: 14–26.
- Xu W and Yu J (2017) A novel approach to information fusion in multi-source datasets: A granular computing viewpoint. *Information Sciences* 378: 410–423.

Xu, J., Zheng, Z., Min, C., Huang, W., & Bu, Y. (2025). Knowledge integration and diffusion structures of interdisciplinary research: A large-scale analysis based on propensity score matching. *Journal of the Association for Information Science and Technology*, 76(9), 1210–1226. <https://doi.org/10.1002/asi.25014>

Zogheib C and Mahetaji K (2024) Cross-Domain Information Integration in Government: Hierarchies and Responsibilities. *Proceedings of the Association for Information Science and Technology* 61(1): 469–480.